

ANALYSIS REPORT
SCC Accreditation No.: 40

Mr Alessandro Picedi
Mondo America

Date: May 17, 2007
 Report: S829-006-19405A

PRODUCT: Drainage pad: FTS K55S
 Received: March 28, 2007; PO#: H000041

STANDARD:

TEST: Water Permeability of Geotextiles by Permittivity ASTM D4491 - 99a (2004)

TEST CONDITIONS: Procedure used: Constant head test;
 Tested April 4, 2007

RESULTS:	Individual Data				Avg.	S.D.	% CV	Spec.
Permeability (E-01 cm/s):	10.0	9.5	9.0	9.0	9.4	0.5	5.1	
Permittivity (s ⁻¹):	0.41	0.37	0.35	0.35	0.37	0.03	7.6	
Flow Rate under 50 mm hydraulic head (gal./min/ft ²):	29.9	27.3	25.5	26.0	27.2	2.0	7.2	

REMARKS: The specimen #1 has been sampled across a groove.

Prepared by:

Maxime Côté
 Maxime Côté,
 Technician

Approved by:

Éric Blond
 For: Éric Blond, Eng., M.Sc.A. Date: May 17, 2007
 Director

****For any information concerning this report, please contact Éric Blond****

The reports are identified by an alphanumeric code, the last character refers to the number of revision(s), this is emitted in ascending order. The samples in relation to this test are retained for a period of 30 days following the expedition day of the written report, unless other instructions are received. The fees for all services after the tests are 125.00 \$ per hour and for appraisal in Court, 195.00\$ per hour. The above reported results refer exclusively to the samples submitted for evaluation. This analysis report cannot be partly used or reproduced, unless in whole, without CTT Group prior written consent.